



ESTIMATE

Tidewater Home Improvement LLC

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

BILL TO

Danny Carlisle

Danny Carlisle

757-912-2242

abcoperations2211@gmail.com

Estimate Number: 1268

Estimate Date: August 30, 2026

Valid Until: September 29, 2026

Grand Total (USD): \$5,434.00

Clean Up & Debris Removal

Remove debris and existing/old vapor barrier from the crawlspace floor; complete haul-off and offsite disposal

1

Vapor Barrier 6mil

Install new 6-mil white vapor barrier over the entire crawlspace floor. Included with the cleanout special.

1

Crawlspace Door

Replace existing crawlspace access door with new PVC door

1

Dehumidifier and Condensation Pump

Install new AprilAire E070 crawlspace dehumidifier with condensation pump; discharge line run out of the crawlspace

1

Electrical

New dedicated breaker run; GFCI-protected electrical connection for the dehumidifier

1

Seal Vents

Seal crawlspace vents for humidity control

1

Grand Total (USD):

\$5,434.00

Notes / Terms

By agreeing to these Terms and Conditions, the customer acknowledges and accepts the outlined responsibilities and scope of work.

Scope: All work described in the Included Scope above. Any work not listed is not included unless agreed in writing.

Structural excluded: piers, joist/beam repairs, subfloor sheet replacement, engineering, foundation modifications.

Owner supplies: none required.



ESTIMATE

Tidewater Home Improvement LLC

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

Contractor supplies: 6-mil vapor barrier, PVC crawlspace door, AprilAire E070 dehumidifier, condensation pump and discharge line, electrical materials, vent-sealing materials.

MEP contingency: if live wiring/plumbing is found during the work, a change order covers rerouting.

Notes:

**Jobsite will be left clean once completed.

**Contractor is not responsible for damage caused inside the home while repairing the foundation.

Warranty:

**12 months workmanship.

Payment Terms:

- Total Project Cost: \$5,434.00

- Deposit to Schedule: \$2,717.00

- Final Payment: \$2,717.00

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Validity: one (1) week from the date above.